ASPHALT INSTITUTE

Annual Sales of Petroleum Asphalt and Road Oil to Domestic Consumers in U.S.A

OF TONS) MILLIONS z -

> 21 8

17 16 2 14 13 12 10

CHARTED BY THE ASPHALT INSTITUTE MARCH 1960 SOURCE: U. S. BUREAU OF MINES ANNUAL FIGURES

75% ROOFING 16% MISCELLANEOUS 9% TOTAL SALES PAVING

*65, 85,

DEFICIAL BASED ON PRELIMINARY ESTIMATES

IND OFFICIAL FIGURES AVAILABLE FOR PERIOD 1920-1930

ASPHALTOPICS

Winning Combination: History of a sort was made by the January issue of the Quarterly when, for the first time, we had to go back on the press for an additional run to meet the demand. Fred Kimble's article on compaction attracted a lot of favorable comment, but the most interesting bulk order came from the Delaware State Highway Department which found a special use for the article on that state's ambitious all-the-way paving program. Chief Right-of-Way Agent H. L. Keene, arming his field people with Quarterlies, reported that the article would help negotiators explain highway needs to property owners.



Somehow we don't usually think of 85-100 penetration asphalt as being an instrument of policy in colonial government, but that's the way it works out in Algiers. After the Algerian rebels were dispersed, their cobblestone barricades were torn down and the stones replaced in the streets. Then a wary government, with a shrewd display of Gallic logic, sealed them

beneath an overlay of asphalt concrete. C'est la guerre!

A note from Joe Draney, the patriarch of asphalt paving, recalls his first job in 1897—weighing out Trinidad lake asphalt from sailing vessels that used to poke their way up the Potomac River to the Washington refinery near Georgetown. Joe says he became enamored of road-building when, as a child on New Jersey Avenue in the District of Columbia, he watched the primitive paving operation when that street was asphalt-surfaced in 1884.

From an official of the duPont Company comes a chatty note, advising us that one of their lady stockholders recently wrote, asking details about a superior type of German road that she had heard about. Further, she wanted to know if duPont couldn't produce this "magic chemical" that was transforming Germany's beat-up autobabns into things of beauty and a joy forever. It finally turned out that the lady had learned second-hand about the asphalt resurfacing program that was reported in the October 1959 Quarterly.

NEW INSTITUTE PUBLICATIONS

Asphalt Mulch Treatment—Slim (12pp.) pocket-sized manual describing in simple narrative style the recommended procedure for using liquid asphalt in combination with straw and hay mulch to promote the growth of vegetation on slopes and flat areas subject to erosion. Manual Series No. 7.

Specifications for Asphalt Cements and Liquid Asphalts —12pp. revised edition of existing pamphlet, incorporating new material, including specification for asphalt cement for undersealing portland cement concrete. Specification Series No. 2.

The Story of Asphalt—A series of five articles published originally in the Christian Science Monitor in December, 1959, now collected and reprinted as a single, fascinating historical account of the development of asphalt technology. An excellent introduction to the subject for the layman, 8pp, Information Series No. 111.

ASPHALT LOUISITUTE

Vol. 12, No. 2

April, 1960

Glynn Harvey Editor

CONTENTS
Asphaltopics 3
Over the River and Through the Woods The Trans-Canada Highway, longest single road-building project in history
It Takes Know-How and Know-Where Asphalt-base section on Kansas Interstate licks shortage of aggregates
Efficient Filtering for Effective Drainage 10 by W. R. Lovering, District Engineer
Index to QUARTERLY Articles (1949-1960) 13
Members and Offices of The Asphalt Institute 15

Cover

Complotion of this few-mile section of asphalt-perved (2½ inches of esphalt concrete on four inches of hot-mix asphalt base) superhighway lest August gave Novada 22 miles of continuous interstate mileage in the Truckee River canyon east of Rene.

-Novada Dept. o Highways Photo



The Asphalt Institute Quarterly is published by The Asphalt Institute, an international nonprofit association appeared by members of the petroleum asphalt industry to serve both users and producers of asphaltic materials through programs of engineering research and education.

The member companies of the institute, who have made possible the publication of this megazine, are listed an page 15.


Articles may be reprinted with credit line. Correspondence should be addressed to the Asphalt Institute Quarterly, Asphalt Institute Building, University of Maryland, College Park, Maryland.


OVER THE RIVER AND



THROUGH THE WOODS







First lift of three-inch asphalt concrete surface course is placed near Banff. Mount Eisenhower in background

cost was hiked to more than \$500 million with the federal contribution climbing to more than \$300 million. Perhaps it was a coincidence that, in 1956, both the Canadian and United States governments came up with a 90-10 sharing proposal to the states and provinces. But the Canadian parliament placed a firm lid on its offer. As an added incentive to the provincial governments to close conspicuous gaps in the route, Ottawa offered to increase its ante to ninety percent of the cost, but limited the offer to ten percent of the total mileage in each province.

Last year, another extension of time was voted with the hope that the last gap in the line will be closed in 1960, and paving completed in 1961. At this writing, about 1200 miles remain to be paved and only a few hundred miles remain to be placed under grading contract.

TWO BIG GAPS

There are two principal gaps remaining in the coast-to-coast highway. One is a 68-mile stretch of tumbling peaks and canyons laced by wild rivers around the northeastern rim of Lake Superior in Ontario. A little more than a year ago this gap stretched for 165 miles through howling wilderness from the Agawa River, 94 miles north of Sault Ste. Marie, to Marathon, a brand new town that has sprung up around a pulp mill. Clearing the required 100-foot right-of-way through this rugged country-considered as spectacular as anything in the Canadian Rockies-was a major lumbering operation. Rock removal and bridging cataracts pushed the cost of road-building in this section to \$325,000 per mile.

Engineers are confident that 1960 will see this 68-mile gap closed, opening the route to travel on a graded gravel through Ontario's high country.


A second gap, and one shot through with special problems, is that stretch of road through four neighboring national parks on the Alberta-British Columbia border. Everyone, including the Canadian army and imported avalanche experts, have been getting into the act. In fact, even the truculent Canadian grizzly bears have been horning into the picture, sabotaging operations with a display of gastronomical virtuosity that deserves passing mention-and will receive it.

SHOOTING THE GAP

When the engineers laid out the route in this section, they had a choice of driving ahead for ninety miles through Rogers Pass in the Selkirk range, or following the water-level route that traces a 190-mile arc to the north, along the course of the Columbia River. The Canadian Pacific Railway already had tried threading the pass back in 1894, but snowslides and avalanches, thundering down from the majestic surrounding peaks, buried that dream. In 1916, the railroad gave it up as a bad job and started running its trains through the Connaught Tunnel which was drilled through the mountains.

In spite of this grim record, the road-builders decided to tackle the beeline route through the Pass again. The economic justification was clear in the face of the dreary alternative-a 100-mile detour along the river bottom. The engineers concluded that we have come a long way in the last 7.5 years in the knowledge of how to control snowslides.

Several methods are employed in this technique. Earth mounds, acting like World War II concrete tank traps, have proved effective in stalling and braking slides. Diverting dams also are used to steer slides away from the road and snow fences are proving effective in preventing the build-up of dangerous overhangs on the peaks. Canadian army teams, armed with mortars and other field pieces, have been bracketing the danger spots on the upper slopes and triggering threatening



slides prematurely with well-placed shots. The engineers plan to place heavy reliance also on several strategically located snow sheds which will protect traffic at vulnerable locations.

BLUE PLATE FOR BRUIN

One method, however, was abandoned by the avalanche experts. They tried planting dynamite charges on the upper slopes, to be set off when roving avalanche spotters recognized the danger symptoms. This didn't work, though, and an investigation explained why nothing happened when the powder monkeys hit the plunger. It seems roaming grizzly bears kept unearthing the dynamite sticks and devouring them like lollipops. Aside from a mild hyperacidity, the bruins apparently thrived on the diet.

A less dramatic, but costlier, problem was presented by the rugged terrain in this area. For example, construction of the 27 miles through Canada's Glacier National Park required the removal of ten million cubic yards of rock, an average of 370,000 cubic yards per mile. Yet, in this nightmare world of rock there is a dearth of suitable aggregates for base construction and surface mix. Limestone outcrops are being investigated to determine the feasibility of starting quarrying

Total thickness of pavement on the Trans-Canada Highway varies with site conditions. However, the asphalt pavement layer is specified as three inches minimum. A typical section in British Columbia calls for 121/2 inches of aggregate base

beneath three inches of hot-mix asphalt concrete laid in two lifts. The three-inch surface course is fairly standard, and the sections built by the federal government require (in addition to the three-inch asphalt concrete surface) that the top three inches of base also be a hot plant mix. Total thickness of base and subbase will vary according to soil and expected

pressure to press for early completion of the project. The provinces and the federal government are anxious to get this herculean job out of the way so they can get on with a new and even more ambitious road program.

Next on the Canadian schedule is her "Roads to Resources" program, calling for the construction of more than 4,000 miles of new roads stretching off into the Canadian boondocks hitherto accessible only by plane or dog sled. These will not be superhighways; they will only be pioneer, allweather roads. Paving will come later on these tiny tentacles of civilization, sometimes called "Roads With a Future."

This stretch of the Trans-Canada Highway in British Columbia



KNOW-HOW


KNOW-WHERE

Cut in pavement section for installation of an inlet box shows full depth of asphalt base on Kansos I-70 project





TYPICAL PAVEMENT SECTION



Typical roadbed cross-section showing heavy four-layer base, two-course paving, high-type shoulders and related features. Dual roadways here are 42 ft. c. to c.

Asphalt-base section is built on Kansas Interstate system by contractor who knew how to lick the aggregate shortage on the plains.

PARCHED by summer sun and scoured by winter storms, the Great Plains of western Kansas can break a man—particularly if he's a farmer or a road-builder. There sometimes isn't enough rainfall to sustain the former, and not enough road-building aggregates to suit the latter.

That's why, when the Kansas Highway Department invited bids last year to construct 22.628 miles of Interstate Route 70 in Trego County, it could have been an invitation to disaster for the unwary contractor.

FIRM WITH FORESIGHT

But the San Ore Construction Company of McPherson had the vision to anticipate the challenge in this part of the state, and the good sense to do something about it. As early as five years ago, the firm staked out a lease on the only important source of crushed stone in that part of Kansas. Ten years ago, the same firm had the foresight to recognize that Kansas sands are deficient in filler particles and took a long-term lease on a large sand pit which produces material which falls into the desirable minus 80 mesh classification.

In addition, the contractor did a good job of reconnaissance in west-central Kansas and was privy to the locations of numerous useful sand pits. Armed with know-how in sandasphalt base construction and the necessary "know-where" for short-haul supplies of aggregates, San Ore was able to bid with confidence on the first asphalt section for the Kansas Interstate-Defense system.

Finally, and of critical importance, the San Ore crews were old hands at meeting the strict Kansas gradation specifications for this type of work and were experienced in laying sand-asphalt base.

ASPHALT BASE SPECIFIED

This section roughly parallels U. S. Route 40, bypassing the towns of Ogallah, Wakeeney and Collyer. The Highway Department, painfully aware of the aggregate shortage on the loamy plains, called for a road-mixed asphalt base design with an asphalt concrete surface—in effect, beefing up the locally available base materials of inferior quality and adding a heavyduty asphalt surface of adequate thickness. This shrewd use

Base materials were windrowed and mixing was done by a mixing train which traveled at rate of a mile in 4 hours



of asphalt has been winning many engineering converts in those geographical areas afflicted with an aggregate deficiency.

This marriage of road-mixed sand-asphalt base to plantmixed asphalt concrete surface is an old story in Kansas. It is a pavement design which has performed handsomely on state primary roads. Adapting the design to Interstate traffic meant simply beefing up the base thickness and tailoring the surface type to the need.

A typical design section for the I-70 pavement shows 11 inches of road-mixed asphalt base, using four percent MC-4 cutback after blending of base materials from windrows. The eleven inches of asphalt base were laid down on six inches of compacted subbase in four lifts, topped with four inches of hot-mix asphalt concrete applied in two courses. The top three inches of asphalt base mix was extended full width to provide a three-inch base for the shoulders which were surfaced with three inches of asphalt plant-mix.

MATERIAL PLACED IN WINDROWS

The base materials, carefully graded, were placed in windrows which were shaped and further blended by motor grader. The asphalt mixing train, straddling the windrow and moving at a rate of about one mile every four hours, applied the cutback and the mixture was aerated until the volatiles were reduced by about fifty percent.

Spreading of the windrow for each lift was performed with an electronically-controlled blade which already had proved itself in grading the roadbed to remarkably close tolerances. Base rolling was done with pneumatic-tire rollers, both self-propelled and tractor-drawn. Use of the subgrade and the compacted base courses as haul roads proved the stability of the foundation construction when, under this type of concentrated wheel loading, there was no evidence of rutting or displacement.

The project involved three separate but adjacent contracts involving 684,440 tons of base and surface aggregates and 3,643,677 gallons of asphalt. Total bid price was \$3,-171,485.43 for an average overall cost of \$208,252 per fourlane mile. Cost of the 15-inch asphalt pavement was approximately \$3.36 per square yard, exclusive of shoulders and ramps.

Spreading of base materials was done by electronicallycontrolled blade for greater uniformity and smoothness



KNOW-HOW


KNOW-WHERE

Cut in pavement section for installation of an inlet box shows full depth of asphalt base on Kansas I-70 project





TYPICAL PAVEMENT SECTION



Typical roadbed cross-section showing heavy four-layer base, two-course paving, high-type shoulders and related features. Dual roadways here are 42 ft. c. to c.

Asphalt-base section is built on Kansas Interstate system by contractor who knew how to lick the aggregate shortage on the plains.

PARCHED by summer sun and scoured by winter storms, the Great Plains of western Kansas can break a man—particularly if he's a farmer or a road-builder. There sometimes isn't enough rainfall to sustain the former, and not enough road-building aggregates to suit the latter.

That's why, when the Kansas Highway Department invited bids last year to construct 22.628 miles of Interstate Route 70 in Trego County, it could have been an invitation to disaster for the unwary contractor.

FIRM WITH FORESIGHT

But the San Ore Construction Company of McPherson had the vision to anticipate the challenge in this part of the state, and the good sense to do something about it. As early as five years ago, the firm staked out a lease on the only important source of crushed stone in that part of Kansas. Ten years ago, the same firm had the foresight to recognize that Kansas sands are deficient in filler particles and took a long-term lease on a large sand pit which produces material which falls into the desirable minus 80 mesh classification.

In addition, the contractor did a good job of reconnaissance in west-central Kansas and was privy to the locations of numerous useful sand pits. Armed with know-how in sandasphalt base construction and the necessary "know-where" for short-haul supplies of aggregates, San Ore was able to bid with confidence on the first asphalt section for the Kansas Interstate-Defense system.

Finally, and of critical importance, the San Ore crews were old hands at meeting the strict Kansas gradation specifications for this type of work and were experienced in laying sand-asphalt base.

ASPHALT BASE SPECIFIED

This section roughly parallels U. S. Route 40, bypassing the towns of Ogallah, Wakeeney and Collyer. The Highway Department, painfully aware of the aggregate shortage on the loamy plains, called for a road-mixed asphalt base design with an asphalt concrete surface—in effect, beefing up the locally available base materials of inferior quality and adding a heavyduty asphalt surface of adequate thickness. This shrewd use

Base materials were windrowed and mixing was done by a mixing train which traveled at rate of a mile in 4 hours



of asphalt has been winning many engineering converts in those geographical areas afflicted with an aggregate deficiency.

This marriage of road-mixed sand-asphalt base to plantmixed asphalt concrete surface is an old story in Kansas. It is a pavement design which has performed handsomely on state primary roads. Adapting the design to Interstate traffic meant simply beefing up the base thickness and tailoring the surface type to the need.

A typical design section for the I-70 pavement shows 11 inches of road-mixed asphalt base, using four percent MC-4 cutback after blending of base materials from windrows. The eleven inches of asphalt base were laid down on six inches of compacted subbase in four lifts, topped with four inches of hot-mix asphalt concrete applied in two courses. The top three inches of asphalt base mix was extended full width to provide a three-inch base for the shoulders which were surfaced with three inches of asphalt plant-mix.

MATERIAL PLACED IN WINDROWS

The base materials, carefully graded, were placed in windrows which were shaped and further blended by motor grader. The asphalt mixing train, straddling the windrow and moving at a rate of about one mile every four hours, applied the cutback and the mixture was aerated until the volatiles were reduced by about fifty percent.

Spreading of the windrow for each lift was performed with an electronically-controlled blade which already had proved itself in grading the roadbed to remarkably close tolerances. Base rolling was done with pneumatic-tire rollers, both self-propelled and tractor-drawn. Use of the subgrade and the compacted base courses as haul roads proved the stability of the foundation construction when, under this type of concentrated wheel loading, there was no evidence of rutting or displacement.

The project involved three separate but adjacent contracts involving 684,440 tons of base and surface aggregates and 3,643,677 gallons of asphalt. Total bid price was \$3,-171,485.43 for an average overall cost of \$208,252 per fourlane mile. Cost of the 15-inch asphalt pavement was approximately \$3.36 per square yard, exclusive of shoulders and ramps.

Spreading of base materials was done by electronicallycontrolled blade for greater uniformity and smoothness



Efficient FILTERING for Effective

A discussion of some important aspects

By W. R. Lovering

District Engineer—The Asphalt Institute
Sacramento, California



This article was presented by Mr. Lovering on March 2, 1960, as part of a panel discussion on "How Should Asphalt Pavement Sections Be Designed for Effective Drainage", held during the Third Annual Highway Conference at the College of the Pacific.

WITH the present trend toward elimination of side ditches and increase in lane width for driver safety, together with full paving of shoulders for greater structural support, the design of adequate drainage features in the pavement structural section has become a complex and demanding requirement of highway design. Consequently, the design and construction of these drainage facilities should no longer be treated as routine. Any drains installed must quickly and effectively remove all free water from the structural section and they must perform this function throughout the entire life of the highway. The problems encountered are, in many respects, approaching those of airport drainage.

All too frequently, when ground water seepage is encountered on a highway project, standard underdrains are installed without any special design, assuming that the underdrain will provide all the drainage required. Culverts for surface runoff are selected with care to provide the needed capacity, but the capacity of the subsurface drainage is scarcely considered. The grading of the filter material, the spacing of the underdrains, and the thickness of the filter blanket used, are all factors that must be analyzed and evaluated with due regard to the soil to be drained and the grades involved.

EVALUATE VARIABLES

These variables are, at best, difficult to analyze due to the seasonal fluctuation in the volume of seepage and variation in

Shoulder cracking caused by water draining into fill slope



permeability with compaction. The variables involved must be evaluated, however, at least approximately, and the drainage designed accordingly, because inadequate drainage will result in a saturated foundation with loss of support. More important, a hydrostatic head may develop in the base sufficient to lift the pavement. A hypothetical example (Figure 1) will illustrate the principles involved:

If we assume a one-foot layer of filter material placed on a sixty-foot width of water-bearing soil with a 2% cross-slope toward an underdrain (hydraulic gradient of 0.02), and if we assume, further, a coefficient of permeability of ten feet per day for the filter material, each lineal foot of this installation will be capable of carrying approximately .37 cubic feet, or less than 3 gallons of water to the underdrain each day. A dripping faucet will produce a pint of water in 10 minutes, or 18 gallons in a day—six times as much water as would be removed by each lineal foot of underdrain conforming to the above conditions.

If the soil beneath the filter material has a coefficient of permeability of only .2 foot per day and a hydraulic gradient of 0.04, the amount of water trying to enter the filter material will be 0.48 cubic foot per day. This excess of .11 cubic foot per day gradually will increase the hydrostatic pressure beneath the pavement and if the pavement is relatively impervious, so that the water cannot escape, the pavement will be lifted and eventually broken by traffic. Actual examples of this have been noted where uplift has been sufficient to create a hazard to traffic.

A CONSERVATIVE EXAMPLE

The illustration cited is admittedly an oversimplification and a more accurate estimate of the hydraulic gradients may be made by the construction of a flow net. It is, however, a conservative example of what is occurring on many of our highways. The assumed conditions cover only what might occur with a uniform and relatively impervious soil. When we consider the possibilities of water-bearing strata of silty gravel or sand, the consequences are even more startling.

Before discussing possible solutions to the above problem, let us first consider the requirements of a satisfactory underdrain:

Water is shown here rising through the pavement on a fill



DRAINAGE

of highway drainage

- 1. It must have sufficient capacity to remove any free water from beneath the pavement. To do this the permeability of the underdrain must be several times the permeability of the soil which is to be
- 2. It must maintain the same permeability throughout the design life of the pavement. To prevent clogging of the drain the filter material must have a grading sufficiently fine to prevent migration of silt particles into the drain from the adjacent soil.

The relative permeability of the materials involved can be determined accurately only by tests, although tests on remolded samples may also be misleading. A working procedure, based on the grading of the materials, was suggested by Terzagi for the selection of filter material gradings. This procedure has been tested and adopted, with certain modifications, by the Corps of Engineers. The criteria are based on the piping ratio determined by the relationship of the maximum size of the smallest 15% and the maximum size of the smallest 85% of both the soil and the filter material. The most important of these criteria are:

To prevent clogging of the filter material, the ratio of the 15% size of the filter material to the 85% size of the material to be drained shall not be greater than 5; and the ratio of the 50% size of the filter material to the 50% size of the material to be drained shall not be greater than 25.

To assure adequate capacity, the ratio of the 15% size of the filter material to the 15% size of the protected soil shall be at least 5.

STANDARD WORKING GRADINGS

The use of the Corps of Engineers' criteria requires the selection of a filter material grading for each installation, depending on the grading of the soil to be drained. This procedure is not practicable for contract bidding unless the requirements may be accurately determined well in advance. For this reason, the California Division of Highways has used standard filter material gradings. These standard gradings have been revised recently. They are much more open than those previously specified and the capacity should be adequate for any fine soils.

These standard gradings, however, while entirely satisfactory for normal conditions, may not be expected to fit all conditions and each installation should be given careful study and evaluation. This critical evaluation will, in most cases, have to be made during actual construction and will, therefore, depend on the alertness of the resident engineer.

Application of the Corps of Engineers' criteria to the new gradings may be of interest in illustrating the type of soil which may be drained most effectively by standard filter mate-



= Peak discharge in Cu. Ft. per day per foot of drain.

Coefficient of permeability in feet per day








FIG. 1





TWO LAYER SYSTEM FOR HEAVY FLOW





rial gradings. It will be noted from Figure 2 that the Type "A" filter material will provide adequate capacity for a soil containing not less than approximately 15% passing the No. 200 sieve. Water-bearing clean sands or gravel will require a much more open grading. The use of a more open grading, however, will undoubtedly lead to clogging by fine soils which are normally interbedded or associated with the coarser water-bearing materials.

How, then, may we provide capacity adequate for the coarser, more open, water-bearing strata without running the risk of eventual clogging of the drain? We may

- Increase the thickness of the filter material. This
 would be equivalent to increasing the size of a culvert for surface drainage.
- Use more closely spaced outlets to reduce the distance the water must travel.
- 3. Design a two-layer drainage system, in which a thin layer of filter material is used to prevent clogging, and a second layer of coarse, very open material is used to supply the drain capacity. This type of installation is illustrated in Figure 3.

TWO-LAYER DRAINS URGED

Two-layer drains have been criticized as not being practical to build. There is no doubt that this type of drain will not be as easy to build as a drain using a single filter material and will also be more expensive, but the matter of practicality should be determined by the cost compared to the effectiveness of the drain. When we consider the cost of the pavement structure that may be lost through defective or inadequate subdrainage, there appears to be little doubt that the additional cost is justified if the drain is effective and prevents pavement failure. Some installations of this type already placed have shown them to be effective in handling larger volumes of seepage.

Finally, let us consider the importance of close inspection and control in the production of filter material. The permeability of the filter material can vary greatly with only minor variations in the grading, particularly in the fine sizes. Figure 4 shows the gradings of two materials, the coarser of which has a permeability 11 times that of the other, but the difference in the grading is only a few percent on the fine sizes. This data is taken from a report in the PUBLIC ROADS magazine for February 1952. The only difference

Typical of California's attention to drainage features is this picture showing asphalt curbing and drainage flume



in the two gradings is the elimination of the six percent of material between the #140 and #200 sieve.

WHEN DRAINAGE FAILS

Considering this striking difference in permeability, it is not difficult to imagine what would happen on a long grade if the filter material were filled to capacity and there was a change in grading which materially reduced the permeability. The effect would be the same as placing a check or dam in a canal. An increase in head would result. The excess water would have to go off on the sides, rise through the pavement, or lift the pavement. Any of these possibilities is objectionable from the point of service of the pavement. Seepage water draining on to a fill slope can cause serious cracking of the fill slope and pavement. Uplift of the pavement may result in complete loss of the pavement structure.

The condition described above may be avoided by rigid control of filter material grading or by increasing the capacity of the drainage so that areas of minimum capacity will be adequate to meet the demands. Installation of cross-drains on grades at frequent intervals will generally be a more positive and economical solution. Cross-drains will provide an outlet for seepage water and, if properly designed and placed, prevent an excessive amount of water from accumulating in the void spaces of the previous drain material.

Cross-drains, to be completely effective, should be placed after the filter blanket and base material have been compacted and should cut completely across these layers. This is necessary because seepage water will frequently flow on top of a compaction plane developed during placing of the base material and, unless the cross-trench cuts this plane, the water will not enter the cross-drain. This is particularly true if the base aggregates have a tendency to degrade under traffic and produce additional fines.

Standard grading filter materials should be adequate for fine grained water-bearing soils but if water is entering through an open material, such as coarse sand or gravel, a special design must be used to provide the capacity required. (See Figure 5)

CONDITIONS DICTATE TREATMENT


The treatment required will be dictated by conditions and volume of water expected, as well as the relative cost of various installations that will provide the capacity needed. The following are recommended for consideration in the order of the amount of flow expected:

1. Two-layer trenches

2. Complete two-layer system

Cross-trenches must also be provided at the lower end of cuts and possibly at other locations on long grades. Cross-trenches should also be provided in sag vertical curves and on the low side of super-elevated curves, particularly on grades.

Structural section drainage must be designed after full and careful consideration of the soils present at each individual area. The drains must have sufficient capacity to drain the area quickly and this capacity must be protected by a properly designed filter barrier that prevents migration of fine materials into the drain. Further, close and constant inspection must be maintained during construction to assure that all portions of the drain are built as designed and function to serve the requirements of the design.



A GUIDE TO THE CONTENTS OF PREVIOUS ISSUES OF THE ASPHALT INSTITUTE QUARTERLY

APRIL 1949—JANUARY 1960

CLASSIFIED BY SUBJECT

AIRFIELDS	Quarterly Issue	Page No.		Quarterly Issue	Page No.
Airfield Pavements for Jet Aircraft	July 1953,	p. 8	HEAVY-DUTY HIGHWAYS (GENERAL)		
Asphalt Airfield Paving	April 1949,	p. 17	Another Oregon Trail	October 1955,	p. 10
Asphalt Overlays Strengthen Airfield Pavements Asphalt Paves Seven of Nation's Ten Leading	July 1953, April 1957,	p. 10 p. 6	A Short Stretch of Highway—Long on Economy and Performance	January 1957,	p. 13
Airports Asphalt—The Paving Choice at San Francisco Airport	January 1955,		Asphalt for the I's of Texas Asphalt Highway Helps Relieve Louisville Con-	January 1959, January 1957,	
Operation Overload (Columbus AFB)	January 1959,	p. 4	gestion		
Some Factors Affecting Airfield Design	July 1953,	p. 4	Asphalt Paves Merritt Parkway Relocation	January 1953,	
ASPHALT RESEARCH AND DEVELOPMENT	AII 10E2	. 1	Big Texas Overlay, The Boston's Circumferential Route is Paved with Asphalt	July 1957, January 1952,	p. 12 p. 4
Asphalt as a Material Asphalt Cements	April 1953, October 1953,	p. 4 p. 10	Custer Makes Another Stand	July 1958.	p. 11
Asphalt Institute Codifies Types of Paving Mixes	April 1957,	p. 11	Frugality in the Foothills (Pueblo Expressway)	October 1959.	p. 8
Asphalt Research	January 1953,	p. 12	Green Hills, Red Barns and Black Roads (Ver-	January 1959,	p. 8
Hybla Valley Research Project:	April 1949,	p. 11	mont I-road) Heavy-Duty Asphalt, the Modern Pavement, Sur-	January 1957,	p. 8
Tests of Asphalt Bases and Pavements Liquid Asphaltic Materials (Cutback Asphalt and	April 1954,	p. 10	faces California's Ben Ali Freeway		
Road Oils)	1	- 30	Heavy-Duty Highways	July 1949,	p. 4
Liquid Asphaltic Materials (Emulsified Asphalts)	January 1955, January 1956,		Heavy-Duty Highways: Test Procedures	July 1959.	p. 6
WASHO: The Asphalt Glory Road CITY STREETS	January 1750,	p. 4	Typical Construction Practices in United States and Canada	July 1949,	p. 7
	1 3050	n 4	"I Have Reached Some Conclusions" (Sweet)	April 1958.	p. 13
American Cities Prefer Asphalt	January 1950, April 1956,	p. 4 p. 8	Louisiana Rolls Out the Magic Carpet	January 1956,	
Chances Are—An Asphalt Street Borders Your Home	April 1930,		Modern Road Building Needs Economy of Asphalt	July 1957,	p. 5
Chicago: City of Big Pavements	July 1959,	p. 4	Construction Nevada Bets the Roll on Black	April 1959.	p. 11
Construction Methods	January 1950,		No Penny-Ante Predicament	January 1959,	p. 3
Easy Does It (Maumee, Ohio) Made for Wear and Tear	July 1959, April 1958,	p. 6 p. 11	On the Navajo Trail	April 1957	p. 12
Pavement of Presidents, The	April 1958,	p. 4	Oregon's New Columbia River Highway	January 1952,	p. 10
Pavements for New Development Areas	January 1950,	p. 9	Paving the Interstate Highway System	October 1956,	p. 3
"Q.E.D." California's Durable Street Pavements	April 1958,	p. 8	Paving the Permafrost Proven Asphalt Design on U. S. 991	October 1958, October 1957,	p. 4 p. 10
Proved the Flexible Theory	1050	- 0	South Carolina's Fine Highway System	January 1956,	
Resurfacing Problems	January 1950, January 1950,	p. 8 p. 10	The Ever-Smooth Highway	April 1957.	p. 3
Street Maintenance Street Scene: 1958	April 1958,	p. 12	They're Out to Improve Iowa's Highways	July 1957,	p. 10
Visalia Revisited	April 1958,	p. 9	Uncorking a Bottleneck in Columbus Wider Highways—Greater Safety—Less Cost	July 1957, April 1956,	p. 13 p. 3
COMPACTION			HYDRAULIC STRUCTURES		
Importance of Proper Compaction	July 1959,	p. 3	Asphalt Cap for Cellular Breakwater	April 1959.	p. 8
Operation Overload (Columbus AFB)	January 1959,	p. 4	Asphalt Cut-Off Wall at Claytor Dam	April 1951,	p. 10
Proper Compaction of Asphalt Pavements	January 1960,	p. 4	Asphalt Has Many Uses in Water Control and Conservation	April 1955,	p. 12
CURBS AND GUTTERS			Asphalt in Hydraulic Works in The Netherlands	April 1955,	p. 4
Asphalt Curbs and Gutters	April 1951,	p. 8	Bridgework - With Asphalt Inlays	October 1956,	p. 12
Better Curbs with Hot-Mix	April 1956,	p. 10 p. 12	Galvestor Jetty	April 1951,	p. 12
Surface Drainage Structures	April 1952,	p. 12	Groins, Harvey Cedars, N.J.	April 1959,	p. 7 p. 4
DESIGN			Montgomery Dam, World's First Asphalt-Faced Dam	April 1959,	
Advance Design Criteria	October 1959,		New York Garbage Scows Lined with Asphalt	April 1959,	p. 10
Asphalt Base for Modern Traffic	January 1960,	p. 3	Paving Levee Slope—Lake Okeechobee, Florida	October 1953, April 1955,	
Asphalt Base (South Carolina) Highway Pavement Design	October 1959, July 1951,	p. 6 p. 4	Paving Los Angeles' Garvey Reservoir with Heavy- Duty Asphalt	April 1955,	p. 9
WASHO: The Asphalt Glory Road	January 1956,	p. 4	Prefabricated Asphalt Lining in Colorado Reser-	April 1955.	p. 11
What About Stage Construction?	October 1959,		voir Reduces Water Seepage	April 1949.	p. 8
FOREIGN			Progress in Developing Asphalt Canal Linings Taming the Mighty Mississippi	January 1960,	p. 12
Germany Turns to Asphalt for Her New Auto- bahns	October 1959,	p. 10	The Asphalt Groins at Ocean City, Maryland The Fernandina Beach Groins	April 1955, April 1955,	p. 6 p. 8
Great Caesar's Ghost (Italy's "Sun Highway")	July 1599,	p. 8			
Italian Paving Is on the Beam	October 1959,	p. 12	MISCELLANEOUS		
Mayan Miracle (Inter-American Highway)	October 1958,		A Balanced Budget for Roads	January 1958,	
Reich Turns to Asphalt	October, 1958,	p. 13	A Salute to the Federal Highway Administrator	April 1957,	p. 4

	Quarterly		ige		Quarterly	P	age
Asphalt Institute Gets a New Home	Issue April 1955,		No.		Issue		No.
Asphalt Paving Puts to Sea	January 1958,		4	Highway Salvage in Delaware	April 1950,		6
Asphalt Speed Paving Record Set	April 1955		6	Highways, Today and Tomorrow Important Considerations in Widening and Re-	April 1950, April 1950,		12
"Aspirin Oval" (Ford Test Track) Auto Racing At Its Best on Asphalt	October 1957, October 1957,		12	surfacing Operations Louisiana's "Floating" Road			-
Bridgework—With Asphalt Inlays	October 1956,		12	Louisiana's "Floating" Road Major Improvements on Long Island	January 1959,		12
Charm and Utility of Asphalt Driveways, The	April 1956,		7	Modernization With Asphalt—Typical "Then and	January 1954, January 1953,	p.	12
Coming: A Year of Decision Drive Up to The Golden Gate on Asphalt	January 1958, October 1956,	p.	11	Now" Resurfacing Views in Washington; Texas			
Extra Added Attractions for Drive-Ins	October 1957,	p.	8	in New Jersey; New England Nevada's Wider Roads	January 1953,		11
Future Trends in Highway Development	April 1949,	p.	4	Ohio Efficiently Prolongs Life of Pavements with	October 1953, January 1953,		8
Highways—Highway Costs—Highway Safety	April 1954,		4	Asphalt			
In Construction the Interstate Highway System— 90% Federal Aid—A Temptation to Neglect Economy	April 1957,	p.	5	Patching and Slab Replacements of Portland Cement Concrete Pavement Sand on the Skyline	April 1953, October 1958,		12
Institute Ad Program Keeps on Rolling	July 1957,		4	Saving and Improving Mid-Western Pavements	April 1950,	p.	. 8
Institute Gets Dow Papers Institute Laboratories, The	April 1958, April 1955,		7 8	Subsealing Rigid Type Pavements with Asphalt Thirty-Seven More Miles of Asphalt Resurfacing	April 1949, April 1956,		13
Institute Launches Major Ad Campaign	July 1956.		4	on Pennsylvania Turnpike	April 2750,	pr.	4.6
More Roads for Less Money	January 1951,			ROAD MARKING			
Natchez Trace P.A.R.—Project Adequate Roads	July 1959, July 1952,		11	Asphalt Center Stripe	April 1951,	p.	13
Patterns in Paving (Asphalt Block)	July 1958,	p.	8	ROOFING			
Stress-Conditioning Flexible Pavements There's An Asphalt Pavement for Your Service	April 1953, October 1956,		6 8	Asphalt in Roofing	April 1953,	p.	. 8
Station State of Service	OCLOBER 1750,	μ.	0	What's New In Roofing	July 1958,	p.	
Three-Way Stretch in Dixle (South Carolina)	October 1959,			SECONDARY ROADS			
We Shall Never be Through with the Job What Loads on What Highways?	January 1960, January 1951,			Asphalt Got 'em Out of the Mud	July 1956,	p.	. 6
"What Neither John Loudon McAdam nor Sir	July 1952,		4	Designing Low-Cost Roads	October 1949,		
Isaac Newton Knew About Road Building,				High Development of Local Roads in Wisconsin Low-Cost Roads:	July 1956,	p.	. 8
Present-Day Soils Experts Do Know" World's Fastest Race Track (Daytona Beach)	April 1959,	p.	12	Cold-Laid Plant-Mix Types	October 1949,	p.	. 10
	- Morti # 22272	je.		Mixed-in-Place Types	October 1949,		. 8
"OLD" ASPHALT ROADS	October 1955.		10	Surface Treatment Types Mayan Miracle (Inter-American Highway)	October 1949, October 1958,		. 6
Another Oregon Trail 41-Year-Old Denver Pavement	July 1951,		12	Texas Farm Road No. 160	July 1956,		10
58-Year-Old Asphalt Pavement in Visalia, Cali-	April 1952,		13	SOIL-ASPHALT ROADS			
fornia Made for Wear and Tear	April 1958,	0	11	Delaware Stabilization Program to Pave All	January 1960,	p	. 8
Pavement of Presidents, The	April 1958,	p.	4	State's Dirt Roads			
"Q.E.D." California's Durable Street Pavements	April 1958,	p.	8	Development of Soil-Asphalt Roads Oiling Earth Roads-Illinois	October 1950, October 1950,		. 13
Proved the Flexible Theory Roncevert Road (West Virginia)	July 1959.	D.	14	Quiet Revolution in Roadbuilding	October 1957,		7
Virginia-The Beginning and the End	July 1958,	p.	12	Sand-Asphalt Roads—Florida	October 1950,		. 12
Visalia Revisited	April 1958,	p.	9	Sandy Loam Stabilization—Nebraska Soil Asphalt Reference Bibliography	October 1950, October 1950,		. 11
PARKING AREAS				Soil Asphalt Roads in Oklahoma	October 1950,	p.	
Asphalt Pavements for Parking Areas Asphalt Pavements—The Top Choice for Park-	January 1950, April 1956,		12	STAGE CONSTRUCTION			
ing Areas	April 1750,	p.	4	An "Old" Road in Louisiana	October 1953,		
PAVEMENT SHOULDERS				From Plank Road to Asphalt Superhighway	October 1955,		. 4
Adequate Highway Shoulders Provide Service	April 1952,	n	4	Life Characteristics of Flexible Pavements North Carolina's Stage Construction Program	July 1951, October 1955,		. 11
and Safety				Stage Construction on U.S. 40, Ohio	January 1954,	p.	. 7
Asphalt Shoulder Construction in California	April 1952,		6	Virginia's Seven Pines Road—After Thirty Years	July 1953,	p.	. 13
California Puts a Shoulder to the Wheel Surface Treatment of Shoulders in South Caro-	October 1958, April 1952,		11	TOLL ROADS AND TURNPIKES			
lina		-		Asphalt To Pave New Jersey Turnpike	January 1951,		
PAVING EQUIPMENT				Equinox Sky Line Drive—Asphalt Paved Florida's Sunshine State Parkway	January 1954, January 1957,		. 4
Equipment Development and Its Influence on	July-October			For 181 Miles of the Kansas Turnpike They	October 1956,	p.	. 10
Construction and Maintenance Procedures	1954,		7	Chose Asphalt Pavement Kansas Turnpike Opens, The	January 1057		12
Slip-Form Paver	April 1951,	p.	9	New Jersey (Construction)	January 1957, October 1951,		. 12
RAILROAD BALLAST				New Jersey ("Still Champion!")	April 1959,	p.	. 14
We've Been Working on the Railroad	July 1959,	p,	12	Oklahoma's Turner Turnpike	October 1952,	p.	. 4
RECREATION AREAS (PLAYGROUNDS, ETC.)				Oklahoma's Turner Turnpike: Design and Construction Details	October 1952,	D	6
All-Season Tennis Courts	July 1950,	p.	6	Review of the Authority's Highway Maintenance			
Asphalt Play Areas-Smooth, Economical, Dur-	October 1956,	p.	4	Study Oklahama Turanika Authority Salasta Asabalt	January 1052	-	7
able Asphalt Skating Rink	April 1951,	D.	13	Oklahoma Turnpike Authority Selects Asphalt for Turner Turnpike	January 1952,	p.	
Asphalt Swimming Pools	July 1950,	p.	10	Pilgrim's Progress (Connecticut Turnpike)	January 1958,	p.	. 12
How to Pave Recreation Areas Improved Surfacing for Drive-In Theaters	July 1950, July 1950,		12	Pride of the Bay State (The Massachusetts Turnpike)	July 1957,	p.	. 7
Ohio State University's Asphalt Tennis Courts	April 1949,		12	Safe Driving on the Turner Turnpike	January 1954,	p	. 10
Paving a Midget Race Track with Asphalt	July 1950,		13	The All-Asphalt New Hampshire Turnpike	October 1953,	p.	. 12
Resilient Paving for Playgrounds	July 1950,	p.	8	The Garden State Parkway	January 1955,	p.	. 4
RESURFACING-WIDENING-UNDERSEALING				The New Jersey Turnpike: Asphaltic Concrete Paving Mixes	October 1951,	0	. 10
A Highway Improvement Project in Texas	April 1950,		11	General Roadway Design Features	October 1951,	p.	. 8
A Major Street Improvement in Denver Another Oregon Trail	October 1953, October 1955,		10	Some Construction Details on the Turnpike The New Jersey Turnpike — One of America's	October 1951, October 1951,		. 12
Asphalt Resurfaces Twenty-Two Miles of Pennsyl-	January 1955,		8	Heaviest-Duty Highways	October 1951,	p.	. 4
vania Turnpike Asphalt "Surrounds" Worn Concrete in Texas	January 1064	m	6	The Will and The Way	January 1958,		. 10
Asphalt Underseal for Concrete Pavements	January 1954, April 1951,	p.	4	"Vacationland" Extends Its Great Asphalt Turn- pike	January 1956,	p.	. 8
Big Texas Overlay, The	July 1957,	p.	12	Virginia—The Beginning and the End	July 1958,	p	. 12
California Transforms Thirty-Foot Road for Super Highway Service	April 1950,	p.	10	* NOTE: Issues of the Quarterly are available thro			
General Outline of Underseal Specifications	April 1951,		6	or member company (see page 15). The issues of	April 1949, July	y 1	949,
Highway Modernization in the Northwest	January 1954,	p.	4	October 1949, and July 1950, are out of stock a (College Park, Maryland).	t Institute head	luar	rters
Highway Modernization Using Asphalt	January 1953,	p.	**	toollege Park, maryianus.			



THE ASPHALT INSTITUTE

EXECUTIVE OFFICES AND LABORATORIES

Asphalt Institute Building Campus-University of Maryland College Park, Maryland

MEMBERS OF THE ASPHALT INSTITUTE

(As of April 1, 1960)

The Asphalt Institute is an international, nonprofit association sponsored by members of the petroleum asphalt industry, to serve both users and producers of asphaltic materials through programs of engineering service, research and education. Membership is limited to refiners of asphalt from crude petroleum. Institute members provide quality products and advocate quality construction and timely maintenance.

ALLIED MATERIALS CORPORATION Oklahoma City, Oklahoma AMERICAN BITUMULS & ASPHALT COMPANY San Francisco and Baltimore AMERICAN PETROFINA COMPANY OF TEXAS ANDERSON-PRICHARD OIL CORPORATION

Oklahoma City, Oklahoma
ASHLAND OIL & REFINING COMPANY Ashland, Kentucky
THE ATLANTC REFINING COMPANY

Philadelphia, Pennsylvania BERRY ASPHALT COMPANY Magnolia, Arkansas BERRY REFINING COMPANY

Chicago, Illinois BRITISH AMERICAN OIL CO. LTD.

Toronto, Ontario, Canada BRITISH PETROLEUM COMPANY LTD. London, England

BYERLYTE CORPORATION

Cleveland, Ohio CANADIAN HUSKY OIL LIMITED

Calgary, Alberta, Canada
CITIES SERVICE OIL COMPANY (PA.) New York, N.Y.
COMPANIA ESPANOLA DE PETROLEOS, S.A.

Madrid, Spain Houston, Texas
COSDEN PETROLEUM CORPORATION

Big Spring, Texas
DERBY REFINING COMPANY
Division of Colorado Oil and Gas Corporation
Wichita, Kansas
DOUGLAS ON CONSTRUCTION Wichita, Kansas
DOUGLAS OIL CO. OF CALIFORNIA

Los Angeles, California D-X SUNRAY OIL COMPANY

Tulsa, Oklahoma
EDGINGTON OIL REFINERIES, INC.

Long Beach, California EMPIRE PETROLEUM COMPANY Denver and Sheboygan, Wisconsin EMPIRE STATE OIL COMPANY

Thermopolis, Wyoming
ESSO STANDARD
Division of Humble Oil & Refining Co.
New York, N.Y.

FARMERS UNION CENTRAL EXCHANGE, INC. Laurel, Montana

GENERAL ASPHALTS, INC A subsidiary of Kerr-McGee Oil Industries, Inc. Oklahoma City, Oklahoma GOLDEN BEAR OIL COMPANY

Los Angeles, California
GREAT NORTHERN OIL COMPANY St. Paul, Minnesota

HUMBLE OIL & REFINING COMPANY Carter Division

Billings, Montana HUNT OIL COMPANY Dallas, Texas

HUSKY OIL COMPANY Cody, Wyoming IMPERIAL OIL LIMITED

Toronto, Ontario, Canada LEONARD REFINERIES, INC.

Alma, Michigan LION OIL COMPANY

A Division of Monsanto Chemical Company El Dorado, Arkansas

MACMILLAN PETROLEUM CORPORATION El Dorado, Ark. and Los Angeles MARUZEN OIL COMPANY LIMITED

Osaka, Japan MOBIL OIL COMPANY

A Division of Socony Mobil Oil Co., Inc. New York, N.Y. MONARCH REFINERIES, INC. Oklahoma City, Oklahoma

NORTHWESTERN REFINING COMPANY St. Paul Park, Minnesota

AB NYNAS-PETROLEUM Nynashamn, Sweden

INSTITUTE ENGINEERING OFFICES

(As of April 1, 1960)

DIVISION I-ATLANTIC GULF

NEW YORK 20, N.Y.—1270 Avenue of the Americas New York City, Long Island and New Jersey

BOSTON 16, MASSACHUSETTS—419 Boylston Street Connecticut, Maine, Massachusetts, New Hamp-shire, Rhade Island, Vermont

ALBANY 7, NEW YORK-11 North Pearl Street New York State (except New York City and Long Island)

HARRISBURG, PENNSYLVANIA-800 North Second Street
Delaware, Pennsylvania

RICHMOND 19, VIRGINIA—Travelers Building District of Columbia, Maryland, North Carolina, Virginia

ATLANTA 9. GEORGIA-881 Peachtree Street, N.E. Florida, Georgia, South Carolina

MONTGOMERY 4, ALABAMA-79 Commerce Street

NEW ORLEANS 18, LOUISIANA-Maison Blanche Suilding Louisiana, Mississippi

DIVISION II-OHIO VALLEY-GREAT LAKES

COLUMBUS 15, OHIO—Neil House Indiana, Kentucky, Michigan, Ohio, West Virginia LANSING 16, MICHIGAN—109 West Michigan Avenue

Michigan, Northern Indiana
LOUISVILLE J. KENTUCKY—4050 Westport Road
Kentucky, Southern Indiana

DIVISION III-MIDWEST

ST. PAUL 4, MINNESOTA-1951 University Ave. PAUL 4, MINNESUTA—1951 University Ave. Colorado, Illinois, Iowa, Idaho, Kansas, Minne-sota, Montana, Missouri, Nebraska, North Dakota, South Dakota, Utah, Wisconsin, Wyoming

PIERRE, SOUTH DAKOTA—104 Journ Land North Dokota and South Dokota CHICAGO 39, ILLINOIS—2631 West Grand Avenue Wisconsin and Metropolitian Chicago SPRINGFIED, ILLINOIS—26061/2 South Sixth Street SPRINGFIED, ILLINOIS—26061/2 South Sixth Street Principles (except Chicago), St. Louis County, Missouri KANSAS CITY 3, KANSAS—2500 Johnson Drive

Colorado, Utah, Wyoming HELENA, MONTANA—Power Block

Kansas, Missouri (except St. Louis Co.), Nebraska DENVER 2. COLORADO—1031 15th Street

PALOMAR OIL & REFINING CORPORATION

Bakersfield, California
PAZ OIL AND TRADING COMPANY LTD. Haifa, Israel

PHILLIPS PETROLEUM COMPANY

Bartlesville, Oklahoma
RAFFINERIE BELGE DE PETROLES, S.A. Antwerp, Belgium
RICHFIELD OIL CORPORATION

Los Angeles, California JEFF P. ROYDER

Houston, Texas
SHELL INTERNATIONAL PETROLEUM COMPANY, LTD. London, England SHELL OIL COMPANY

New York and San Francisco SHELL OIL COMPANY OF CANADA, LTD.

Toronto, Ontario, Canada SINCLAIR REFINING COMPANY

New York, N.Y.
SOCAL OIL & REFINING COMPANY Huntington Beach, California

SOUTH AFRICAN TORBANITE MINING AND REFINING CO. LTD. Boksburg North, Transvaal

THE SOUTHLAND COMPANY Yazoo City, Mississippi STANDARD OIL COMPANY OF BRITISH COLUMBIA, LTD. Vancouver, B.C., Canada
THE STANDARD OIL COMPANY

An Ohio Corporation Cleveland, Ohio SUN OIL COMPANY

Philadelphia, Pennsylvania
UNION OIL COMPANY OF CALIFORNIA

Los Angeles, California
U. S. OIL AND REFINING COMPANY Los Angeles, California

WILSHIRE OIL COMPANY OF CALIFORNIA Los Angeles, California
WITCO CHEMICAL COMPANY, INC.
Pioneer Products Division

New York, N.Y.

DIVISION IV-SOUTHWEST

DALLAS 6, TEXAS—Meadows Building
New Mexico, Oklahoma, Texas AUSTIN 1, TEXAS-Perry-Brooks Building

OKLAHOMA CITY 2, OKLAHOMA-Republic Building

SANTA FE, NEW MEXICO—10 Radio Plaza New Mexico, Western Texas

DIVISION V-PACIFIC COAST

BERKELEY 10, CALIFORNIA-810 University Ave. Alaska, Arizona, California, Hawaii, Nevada, Oregon, Washington

LOS ANGELES 17, CALIFORNIA-1709 West 8th St. Arizona, Southern California
OLYMPIA, WASHINGTON—National Bank of Com-

merce Building Alaska, Washington

SACRAMENTO 14, CALIFORNIA-Forum Building Central California, Northern California, Nevada PORTLAND 1, OREGON-2035 S.W. 58th Avenue



